



Estimate of Time Required

Route FAU 2678 (N. York Street)
 Section 20-00198-00-RS
 County DuPage
 Project 0CWV(504)

Item	Unit (Check One)	Quantity	Rate Per Day	Days	Days Not Affecting Time	Total Days Required
	<input checked="" type="checkbox"/> English <input type="checkbox"/> Metric					
EARTH EXCAVATION	CU YD	165.00	750.00	0.22		1.00
CURB AND GUTTERS	FOOT	3,663.00	300.00	12.21		12.00
MAST ARM ASSMBLY & POLE	EACH	8.00	2.00	4.00		4.00
SODDING	SQ YD	1,788.00	1,000.00	1.79		2.00
ADJUST FRAMES AND GRATES	SQ YD	74.00	5.00	14.80		15.00
STORM SEWER	FOOT	35.00	75.00	0.47		1.00
PATCHING CLASS C & D	SQ YD	1,720.00	100.00	17.20		17.00
HMA BASE COURSE WIDENING 7"	SQ YD	212.00	500.00	0.42		1.00
HMA SURFACE REMOVAL	SQ YD	34,408.00	5,000.00	6.88		7.00
HMA SURFACE	TON	3,950.00	500.00	7.90		8.00
PCC SIDEWALK REMOVAL	SQ FT	7,389.00	1,000.00	7.39		7.00
PCC SIDEWALK	SQ FT	12,972.00	1,000.00	12.97		13.00
PAVEMENT MARKING LINE (TRUCK)	FOOT	13,605.00	60,000.00	0.23		1.00
PAVEMENT MARKING SYMBOL (HAND)	SQ FT	844.00	500.00	1.69		2.00
STAMPED COLORED PCC MEDIAN SURFACE	SQ FT	2,700.00	200.00	13.50		14.00
AGGREGATE SUGGRADE IMPROVEMENT	SQ YD	360.00	100.00	3.60		4.00
Total Actual Working Days Required						110.00
Total Days from page one						
Total Days						110.00

Made by Matt Quinn Date 11/2/2022 Checked by Matthew Cesario Date 11/2/2022
 _____ Regional Engineer